

February 19, 2010


Page 1 of 1
Our File: 302-962

TOWN OF OSOYOOS
NORTHWEST SECTOR SANITARY SEWER – PHASE 1

CONTRACT DOCUMENTS AND SPECIFICATIONS
ADDENDUM #1

This Addendum is being issued prior to the closing of Tenders and is intended as clarification and/or revision of the Contract Documents. This Addendum shall become an integral part of the Contract Documents and Tenderers shall acknowledge receipt on the appropriate page of the Form of Tender.

- (1) Bidders are to assume the Fortis pole to service the lift station will be within 20.0m of the kiosk. Allowance should be made for conduit, cable, pilaster per FortisBC specifications.
- (2) The quantity of 1500W heaters is hereby changed from one (1) to two (2).
- (3) On drawing 302-962-E2, detail KIOSK 'A' – side "A" elevation "A", the item labeled as "1" beside Item "9" should be item "21".
- (4) Transfer Switch and Generator Receptacle is included.
- (5) There are two light fixtures in Kiosk 'A' and two door switches.
- (6) There will be no wire required in 50Ø DBII duct to radio antenna base.
- (7) All cables (motor and instrument) shall terminate at the kiosk in the termination compartment. Explosion proof seals shall be installed between side "C" of Kiosk 'A' and the rest of Kiosk 'A'. Note that side "C" is to be completed sealed from the rest of the kiosk. There will be no field junction boxes for the motors; only those in side "C".
- (8) 53mm conduit for fibre should be stubbed to outside the kiosk.


Steve Underwood, P. Eng.

SU/cab

M:\My Documents\302\302-962\Tender Documents\Addendum-1.doc